HASSAN DIVISION.

The 20th June 1896.

Tenders are hereby invited for constructing a new sandal koti at Hassan.

2. The plans, detailed estimates, and conditions may be seen at the Executive Engineer's office between the hours of 11 A. M. and 4 P. M. daily.

3. Printed forms of tender will be supplied on application, free of cost, by the Executive Engineer. These forms should be filled in, signed by the contractor and forwarded in sealed covers to the Executive Engineer before the 20th July 1896. The work should be completed by the end of June 1898.

4. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any tender.

5. No tenders will be received unless accompanied by a deposit of Rs. 300 as earnest money.

6. Within eight days of the acceptance of the tender, the contractor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled, and his earnest money will be taken to meet any loss that may be sustained by Government.

7. The name of the contractor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries respecting the acceptance or rejection of a tender will receive any reply whatever.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned to applicants in due course.

9. An approximate estimate quantities of items of works required are given below :—

10. These quantities are not guaranteed.

Items of work.	*Per.*	*Quantity.*
Earthwork excavation	C. yds.	492
Brick in mortar	C. ft.	35,507
Do in cement	,,	1,538
Do in clay	,,	6,552
Arch work	,,	68
Stone slabs	Sq. ft.	1,013
Plastering with mortar	Sqrs.	268·51
Roofing with first class Mangalore tiles with teakwood reepers, nails, &c., complete, including ridging, &c.	,,	205·42
Teakwood work wrought and put up	C. ft.	2,341
Ironwork to trusses	Lump sum.	
Teakwood heaveboards	R. ft.	1,138
Do doors and windows	Sq. ft.	416
Flooring with concrete	C. ft.	226
Do with gravel	C. yds.	645
Bamboo rind matting	Sqrs.	4·80
Whitewashing two coats	,,	186·81
Tarring	,,	54·00
Red painting	,,	12·06
Gattering to valleys	R. ft.	58
Teakwood gate	Each	1
Gate to compound	,,	1
Levelling ground and fencing	Lump sum.	

The 26th June 1896.

Tenders are hereby invited for constructing super-passages, &c., on improving and extending north channel of Sriramdevar dam.

2. The plans, estimates, schedule of rates and conditions may be seen at the Executive Engineer's office between the hours of 11 A. M. and 4 P. M. daily.

3. Printed forms of tender will be supplied on application, free of cost, by the Executive Engineer. These forms should be filled in, signed by the contractor and forwarded in sealed covers to the Executive Engineer before the 25th July 1896. The work should be completed by the end of June 1897.

4. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any tender.

5. No tenders will be received unless accompanied by a deposit of Rs. 300 as earnest money.

6. Within eight days of the acceptance of the tender the contractor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled and his earnest money will be taken to meet any loss that may be sustained by Government.

7. The name of the contractor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries respecting the acceptance or rejection of a tender will receive any reply whatever.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned to applicants in due course.

9. An approximate estimate of quantities of items of works required is given below :—

10. These quantities are not guaranteed.

Items of work.	*Per.*	*Quantity.*
Constructing super-passage across Koglihalla and channel deviation—		
Earthwork excavation	C. yds.	11,944
Removing boulders	,,	100
Earthwork used for bund	,,	2,975
Rough stone work, new	,,	554
Jelly felling	,,	250
Clearing site and excavating foundation	Lump sum	
Rough stone in surki mortar	C. ft.	2,905
Burnt brick do	,,	5,565
Plastering do	Sqr.	3,000
Cut stone work	C. ft.	265
Burnt stone slabs	S. ft.	1,579
Surki concrete	C. ft.	919
Improving Tarahalli Vod—		
Earthwork excavation	C. yds.	563
Rough stone in surki mortar	C. ft.	6,765
Burnt brick do	,,	8,715
Plastering	Sqrs.	37·44
Cut stone work	C. ft.	686
Burnt stone slabs	S. ft.	5,875
Surki concrete	C. ft.	3,675
Distribution and scouring sluices—		
Excavation	C. yds.	36
Rough stone in surki mortar	C. ft.	707
Burnt brick in do	,,	566
Burnt stone slabs	S. ft.	386
Plastering	Sqrs.	7·00
Rough stone work, new	C. yds.	6
Teakwood shutters with iron strips, &c., tarring	C. ft	52

A. S. NAGAVKAR, *Executive Engineer.*

FRENCH ROCKS DIVISION.

The 27th June 1896.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, French Rocks division, up to the 19th July 1896, for restoring the Hagalhalli tank, registered No 224, of Mandya taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of November 1897.

2. The plans, detailed estimate, and conditions may be seen at the Executive Engineer's office at French Rocks between the hours of 11 A. M. and 5 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer, and accompanied by a statement in the form given below showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 250 in cash or Government Promissory Notes as earnest money, and be superscribed "Tender for restoring the Hagalhalli tank, registered No. 224, Mandya taluk"; in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.